Bruhat Bangalore Mahanagara Palike

Office of the Horticulture Superintendent Rajarajeshwarinagar Zone

Name of the Work:-Maintainance of Park in Jalahalli in ward- 16

	Code:	Estimate Cost: 5.00 Lakhs			
	DESCRIPTION OF WORK	UNIT	QTY	RATES	AMOUNT
	Total Park Area : Sqm Total Hardscape area : Sqm Total area left for Landscape Development: 700 Sqm				
	SITE /JUNGLE CLEARENCE:				
	Cutting and clearing thin jungle including removal of roots with a intitial lead of 50 m and life of 1.50 m and **General Cleaning:** Removal of dried leaves, solid waste and cleaning of the area	Sqm	700	8.50	5950
2	**Shrubs in Groups**				
a	Developing the area for shrubs by digging to a depth of 0.45m, filling 50% with sand [0.0375 Cum], FYM [0.075 Cum], Red earth [0.21], [I.e. in the proportion of 1:2:3] and planting with well established plants (8 plants per sq mtr) exclusive of cost of plants and inclusive of ingredients	Sqm	200	435.00	87000
b	Cost of the Plant (8 Plants per Sqm) including Transportation and Handling Charges	Sqm	200	600.00	120000
	Planting of specimen plants				
3	Digging pits size 0.75m x 0.75m x 0.75 filling up to 50% the pits with top excavated soil and remaining 50% with sand, Fym, Red earth (0.021 Cum) (i.e. in the proportion of 1:2:3) and planting of **Ficus Benjimina Prestige** (90cm - 150cm ht) / **Ficus Benjimina starlight**(90cm - 150cm ht) **Ficus Benjimina Black**(90cm - 150cmm ht) / **Ficus Nuda / mini luccii** (90cm - 150cm ht) / **Ficus Panda** (90cm - 150cmm ht) ht) **Ficus traingularis** Including cost of plant, materials, transporation and handling & planting Cost)	Each	30	2500.00	75000
4	Digging pits size 0.75m x 0.75m x 0.75 filling up to 50% the pits with top excavated soil and remaining 50% with sand, Fym, Red earth (0.021 Cum) (i.e. in the proportion of 1:2:3) and planting of **Plumeria Alba** / Rubra (150cm - 240cm ht) Pulmeria Rubra (150cm - 240cm ht) Including cost of plant, materials, transporation and handling & planting Cost)	Each	20	3000.00	60000
5	Digging pits size 0.75m x 0.75m x 0.75 filling up to 50% the pits with top excavated soil and remaining 50% with sand, Fym, Red earth (0.021 Cum) (i.e. in the proportion of 1:2:3) and planting of **Bambusa Ventricosa (90 - 120 cm ht) Bambusa Vulgaris (150cm - 240cm ht) Bamboo Varigated (120cm - 150cm ht)** Including cost of plant, materials, transporation and handling & planting Cost)	Each	43	1200.00	51600
	Supplying of Red Soil (New Earth Filling)				
6	Supply of Good Quality Red Soil for Gardening and Growing of Plants, Shrubs, Etc., Including the % weightage given to B.B.M.P. Area.	Cum	100	438.75	43875

Scanned by CamScanner

inkler System: Providing and fixing of sprinkler system with in the site by using mm/10kg,40mm/6kg, 50mm/6kg good quality PVC pipes,ISI marked sprinklers, ntrol valves and fitiings etc, Including excavation and back filling trenches, Excluding of Providing Borewell , Electrification & pump). As per the specification d direction of the concerned officer. Rates may be quoted as per data rate specific to the field condition.	Each	8	4000.00	32000
Total				475425
N.C.S. Charges 5%				23771
Miscellaneous				803.75
Grand Total				500000.00

(Rupees: Five Lakhs Only)

Sd/-
Horticulture Superintendent
Rajarajeshwarinagar Zone

Asst. Engineer,
Ward No.16
BBMP

Asst Executive Engineer
Yeshwanthpura Sub Division
BBMP

Executive Engineer
R R Nagara Division
BBMP

ನಂ.: 198 ದಿನಾಂಕ: 22/2/19
ರೂ. Five lakes only
ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಉಪ ... ಮಂಜೂರಾತಿ ನೀಡಿದೆ.
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
... ಸಂಪಿ, ಬೆಂಗಳೂರು-72

ನಂ.: 122 ದಿನಾಂಕ: 22/2/19
ರೂ. Five lakes only
ಗಳ ಅಂದಾಜು ... ಮಂಜೂರಾತಿ ನೀಡಿದೆ.
... ಅಭಿಯಂತರರು
..., ರಾಜರಾಜೇಶ್ವರಿ
... ವಲಯ, ಬೆಂಗಳೂರು

Scanned by CamScanner